

COMPETITIVE QUOTATIONS AWARDED

Title	Description	Date of Contract	Contractor	Amount
2016 Bishop Farms Purple Martin Lake Culvert Stabilization	Contractor shall dismantle existing box culvert sections that have shifted or moved into sections less than 5' across in any direction. All exposed steel and asphalt shall be removed. Existing bank on each side of culvert shall be shaped to provide a 2 to 1 slope. Broken pieces of dismantled box culvert shall be placed along the bottom of the creek and on the bank to provide stabilization. Existing sections of culvert that have not shifted shall be protected.	February 1, 2016	Elder Corporation	\$66,200.00
Repair 36" PCCP Feeder Main in Water Works Park	Excavate over two joints on each side of bad section of pipe, remove existing diaper, and confirm joints are sound and in good condition. Get measurement for section of pipe that is bad. DMWW will order new pipe and provide to contractor with an estimated 4-5 day lead time to get new pipe. Remove damaged section of pipe. Install new pipe, having swabbed new pipe with bleach solution. Install cathodic protection cables. Backfill hole. DMWW will do site restoration work.	February 16, 2016	Raccoon Valley Contractors, LLC	\$42,021.00

Item IVD